430 N Grove St. Kewanee, IL

Description of Work
Replace existing water heater with new high efficiency 50-gallon electric water heater
Evaluate and redo all accessible supply and waste plumbing in basement as needed to bring up to code requirements.
Replace existing furnace with new high efficiency natural gas furnace. Minimum 95% AFUE
Provide and install new electrical panel to meet all code requirements, utilize existing electrical service Remove existing bathroom flooring and base trim. Furnish and install new resilient flooring and
prefinished wood base trim.
Install new bathroom exhaust fan with light, vented to exterior per code requirements
Replace existing toilet with white, tall, elongated bowl toilet.
Replace existing vanity with new pedestal sink with surface no higher than 34" above finish floor. Install new single lever operated Delta lavatory faucet.

Bedroom #2	Remove any furniture from room and cover with plastic/tape any items to be protected. Scrape loose, cracked, peeling, blistered surfaces. Fill all holes/cracks, spot prime unpainted surfaces as needed. Clean surfaces prior to painting. Apply (2) coats of finish paint to all walls and ceiling in paint color of owners choosing.
Bedroom #2	Replace bedroom ceiling fan. New ceiling fan to be minimum 42'' fan and to have light
Exterior	Remove and replace 1 windows with new vinyl windows. New windows to be vinyl, single hung minimum U30 rating. Remove stickers and clean windows upon completion. Insulate and weather seal.Bedroom #2
Exterior	Replace storm door at front entry
Exterior	Remove and replace existing back door with new fiberglass door. Install new door hardware; keyed lever and deadbolt. Ensure proper air sealing and insulation during installation.
Kitchen	Repair kitchen sink waste plumbing to ensure proper drainage and meet all code requirements
Kitchen	Install new flush mounted LED light fixture in kitchen.
Kitchen	Furnish and install new refrigerator - basis of bid basis of bid Whirlpool model #WRT318FZDM

Kitchen	Replace existing kitchen receptacles with GFCI receptacles. Install new cover plates.
Living Room	Replace existing living room flooring with new LVP flooring. LVP flooring product to have minimum 6 mil wear layer. Remove base trim and install new pre-finished base to match existing.
Throughout	Install new sealed smoke detectors throughout home to meet code requirements